

**CLARIFICATIONS / AMMENDMENTS TO TENDER DOCUMENT OF SUPPLY,
INSTALLATION, TESTING & COMMISSIONING, AND MAINTENANCE OF VERTICAL
TRANSPORTATION SYSTEM (LIFTS) FOR FACULTY OF COMPUTING BUILDING OF
SOUTHERN CAMPUS, KDU AT SOORIYAWEWA**

Sr No	Description with the clause of tender document	Clarifications by Bidders	Employer Recommendations/ Amendments
1	Clause 2 Vertical Transportation System of the building shall consist of two (02) Passenger Lifts–Machine Room type (MRL)	Whether it is Machine room less (MRL) or Machine room (MR)	It should be Machine Room (MR) type
2	Clause 3.1 • Pit Depth (Available) - 2000 mm	Bidder's requirement is 1500 mm. Whether the filling is to be done as per bidder's requirement.	Employer will do the required filling of pit as required by the bidder
3	Clause 2.24.2 The car of the passenger lifts shall include a fitted stainless steel finished handrails on side walls, wall protectors/Hand rails shall be fitted to all 3 sides of the car inside at a 875 mm height.	Whether it is required to have handrails on both side wall and rear wall handrails or only on the rear wall.	stainless steel finished handrails shall be fitted on side walls, wall protectors/Hand rails shall be fitted to all 3 sides of the car inside at a 875 mm height.
4	Clause 3.5 Car operating panels (2 nos. of COP per lift) shall be mounted on front return panels on both sides the cabin door for better operational convenience with call buttons of micro touch type, which will illuminate on registration of a call	Since the cabin size is 1400 mm x 1350 mm, whether it is required the second COP on the next front return panel.	Amended the quantity of COPs as 01 No. COP per lift on one side of the front return panel
5	Preamble to the BOQ	Whether storage facilities are provided by client.	Employer will provide the storage facilities for materials
6	Preamble to the BOQ	Whether all the required Civil works are done by client.	Employer will arrange required civil works
7	Preamble to the BOQ	Whether power supply with the required cable and breakers are provided in the machine room by client.	Employer will provide the power supply with the required cable and breakers in the machine room. (Internal distribution to be carried out by the bidder).
8	Preamble to the BOQ	Whether bidders can have the scaffolding at site	Employer will permit to have scaffoldings at site

9	Landing Architrave: All landing architrave shall be wide splayed made with hairline finish stainless steel of SUS 304 or higher.	Whether the Jamb type is Wide or Narrow Jamb type	Employer amended the jamb type as "Narrow".
---	--	---	--

Note: Aforeward amendments are recommended by
the TEC.



Member TEC
LCDr PMKC Chandanai.